

The following changes are effective immediately and shall be incorporated into the Contract Documents.

DOCUMENTS

1. ESA Requested Inspection Outcome Summary Report
 - a. Refer to the attached report for the review of the existing Electrical Room 2 at the arena.

SPECIFICATIONS

N/A

DRAWINGS

1. Drawing E1.1 – Clarence Creek Arena Electrical Layout
 - a. The conduits smaller than 2in shown on detail 4/E1.1 can be substituted by rigid PVC conduits.
2. Drawing E1.1 – Clarence Creek Municipal Garage Electrical Site Plan and Details
 - a. The conduits smaller than 2in shown on detail 2/E1.1 can be substituted by rigid PVC conduits.
3. Drawing E2.1 – Clarence Creek Arena Single Line Diagrams and Details
 - a. Delete the housekeeping pad shown on detail 4/E2.1
 - b. Provide 3/4 in fire rated plywood backing, painted grey, in Electrical room 2 and Storage room for the support of bus gutter, disconnect switch and transfer switch.
4. Drawing E2.1 – Clarence Creek Municipal Garage Single Line Diagrams and Details
 - a. Provide 3/4 in fire rated plywood backing, painted grey, in Electrical room for the support of the disconnect switch and generator annunciator panel.

END of ADDENDUM NO 2



400 Sheldon Dr, Unit 1, Cambridge, ON , N1T 2H9

For inquiries:

TOLL FREE TEL: 1-877-372-7233

TOLL FREE FAX: 1-800-667-4278

www.esasafe.com

Requested Inspection Outcome Summary Report

WSP CANADA INC
1345 ROSEMOUNT AVE
CORNWALL ON K6J 3E5

PRINT DATE: May 10, 2018
CUSTOMER ID: 55696
FAX NUMBER:

Notification: 15908760
Cust Order #: 17105729-00

Status: Passed

Code: Final Requested

Site:
CLARENCE CREEK ARENA
418 LEMAY ST
CLARENCE ROCKLAND ON K0A 1N0
