

SCHEDULE OF PRICES

ITEM NO.	ITEM	OPSS NO.	EST. QTY.	UNIT	UNIT PRICE	TOTAL AMOUNT
	PART "A" SITE PREPARATION					
1	Supply and install silt fence barrier	805 & S.P.	12.0	m		
2	Straw bales (by location)	805 & S.P.	2	each		
3	Topsoil stripping, clearing and grubbing of existing shrubs and vegetation (prior to placing fill)	S.P.	1	L.S.		
4	Mass Earth Movement i) Supply, place and compact fill	S.P.	1	L.S.		

SUB-TOTAL PART "A" _____

TENDERER'S INITIALS _____

ITEM NO.	ITEM	OPSS NO.	EST. QTY.	UNIT	UNIT PRICE	TOTAL AMOUNT
	PART "B" STORM SEWERS AND DITCH					
1	Road catchbasin c/w 200mm dia. PVC SDR 35 lead from catchbasin to ditch	407 & S.P.	2	each		
2	Supply and install 1.5m long, 300mm dia. CSP c/w rodent screen		2	each		
3	Supply and install gabion stone (100-200mm) - 0.4m thick ($\pm 4m^2$)		3	L.S.		
4	Re-direct existing ditch centerline		285.0	m		
5	Reinstate ditch with 100mm thick layer of topsoil and hydroseeding		1	L.S.		

SUB-TOTAL PART "B" _____

TENDERER'S INITIALS _____